



NOTES:

- 1 PROVIDE 1' MINIMUM SELECT GRANULAR BORROW AROUND COPPER WATER SERVICE, CORPORATION/MAIN, AND CURB STOP.
- ② CONSTRUCT "GOOSENECK" ADJACENT TO CORPORATION TAP.
- ③ SUPPORT CURB STOP BOX WITH SOLID CONCRETE BRICK.
- ④ CONNECT TO EXISTING WATER SERVICE OR CAP FOR FUTURE CONNECTION.
- ⑤ PROVIDE 2"x2" WOOD MARKER POST FOR FUTURE CONNECTION LOCATING.
- ⑥ MAINTAIN 7.5' MINIMUM COVER THROUGH ROADWAY.
- ⑦ ADJUST CURB STOP BOX TO FINISHED GRADE.

DATE REVISED

10/28/08

COPPER WATER SERVICE

PLATE NO.

2-01