



NOTES:

1. THE CONTRACTOR SHALL INSPECT SILT FENCE AREAS ON A WEEKLY BASIS AND WITHIN 24 HOURS OF EACH 1/2"+ RAIN EVENT FOR ANY DAMAGE AND FILLING OF THE SILT FENCE. ANY REPAIRS OR MAINTENANCE OF THE SILT FENCE SHALL BE ACCOMPLISHED WITHIN 24 HOURS OF THE RAIN EVENT AS DIRECTED BY THE ENGINEER.
2. THE CONTRACTOR SHALL REMOVE SILT FENCE UPON FINAL STABILIZATION, AS DEFINED IN THE MPCA GENERAL STORMWATER PERMIT, OR AS DIRECTED BY THE ENGINEER.

DATE REVISED

05/02/11

SILT FENCE

PLATE NO.

4-03