



NOTES:

1. STABILIZED VEHICLE ENTRANCE SHALL BE CONSTRUCTED AS SOON AS POSSIBLE AFTER THE PROJECT CONSTRUCTION BEGINS TO MINIMIZE TRACKING OF SOILS ONTO EXISTING ROADWAYS.
2. THE CONTRACTOR SHALL MAINTAIN THE STABILIZED VEHICLE ENTRANCE THROUGHOUT THE PROJECT AS DIRECTED BY THE ENGINEER AS AN INCIDENTAL ITEM TO STABILIZED VEHICLE ENTRANCE CONSTRUCTION.
3. TRACKED SEDIMENT MUST BE REMOVED WITHIN 24 HOURS FROM ANY PAVED SURFACE INCLUDING BORROW PIT ENTRANCES, AND ANY OTHER AREAS THAT ARE AFFECTED BY THE CONTRACTOR'S CONSTRUCTION OPERATIONS.
4. THE CONTRACTOR SHALL REMOVE STABILIZED VEHICLE ENTRANCE UPON COMPLETION OF THE PROJECT AS AN INCIDENTAL ITEM TO CONSTRUCTION ACTIVITIES.

DATE REVISED

03/01/08

STABILIZED VEHICLE  
ENTRANCE

PLATE NO.

4-04